A proposal for
CITY OF JOPLIN, MO
FINANCE DEPARTMENT
JOPLIN, MO 64801

Quote # SF-2025-01279 Revision # 1

Nov 20, 2025

Quotation valid until: Feb 18, 2026

This document outlines a comprehensive truck package, comprising the following equipment. The listed equipment is designed to be installed and operated as an integrated system, ensuring full compatibility and optimal performance.

Plow Hitch

Mark E Dump Body

Chassis

Installation

Quote prepared by: Cole Bruemmer

NASPO ValuePoint SUPPLIER PARTNER

npp gov National Purchasing Partners Government Since 2005

Package Model - PACKAGE

HITCH	
Truck Side Hitch Type	**Low Profile**
Hitch Family	**Basic Hitch**
Lift Cylinder	**3"x2" Cylinder Nitrided**
Hitch Width	**30.5"**
Hitch Connection Type	**Quick Hitch**
Hitch Mounting Hardware	**No Mounting Hardware**
HPI	
Family	**Mark E, Classic**
Floor Length	**15' Floor Length**
Side Height	**30 inches**
Body Material (Sides/HeadSheet)	**7GA 201SS Sides/Headsheet**
Floor Material	**3/16" AR400 Floor**
Front Bolster	**No Front Bolsters**
Rear Bolster Material	**7GA 201SS Rear Bolsters**
Rear Bolster Height	**8" Taller Than Sides Rear Bolster, 2 1/8" Pockets**
Top Rail/Rub Rail Material	**7GA 201SS Top & Rub Rails**
Side Braces	**(2) V Crimp Side Braces**
Hydraulic Lines	**No Hydraulic Lines**
Hoist Type	**Trunnion Mount Hoist, Internal DH,DA**
Cylinder Model	**CS/G4,Dbl Act, 2yr Salt Warranty**
Install Hoist & Cradle	**Upfitter Installed H&C**
Hoist Mount Type	**Standard Width Cradle**
Longsills	**10" I-Beam LS, Skip Weld Longsill & Apron**
Body Hinge Maintenance	**Greaseless Bushings**
Tailgate Style	**Configured Tailgate**
Tailgate Air Valve	**Upfitter Supplied Air Valve**
Tailgate Pin Lanyards	**No TG Pin Lanyards**
Horizontal J-Hooks	**Horizontal J-Hooks**
Bolsters Chain Hooks	**Banjo Chain Hooks (Inst)**
Tailgate Chains	**Zinc Plated TG Chains**
Tailgate Hinge	**Standard 1-1/4" Pins, 1" Plate**
Tailgate Release & Control	**Double Acting Air Cylinder with SS Bushings**
Tailgate Lift Style/Location	**Single Center D-Ring,Interior**
Tailgate Brace	**(1) Horizontal Tailgate Brace**
Coal Chute	**No Coal Chute**
Tailgate Liner	**No Tailgate Liner**
Tailgate Sheet Material	**7GA 201SS Tailgate Sheet**
Tailgate Maintenance	**Greaseless Pins, Jaws, & Shaft**
Cabshield Install/Ship Loose	**Cabshield Shipped Loose for Install**
Rear Facing Cabshield Light Holes	**No Rear Light Holes**

NASPO ValuePoint SUPPLIER PARTNER
npp gov National Purchasing Partners Government Since 2005

Side Facing Cabshield Light Holes	**1 Each Side 45 Degree**
Foward Facing Cabshield Light Holes	**No Forward Light Holes**
Cabshield Installation Height	**Upfitter Installed Standard Leg Height**
Cabshield Material	**10 Gauge Sheet 7 Gauge Ends**
Cabshield Width	**86" Width**
Cabshield Overhang	**22" Overhang**
Cabshield Style	**Weld-On Cabshield No Tarp Shroud**
Cabshield Finish Prep	**Cabshield No Finish Prep (Raw)**
Cabshield Paint/Finish	**Cabshield No Finish (Raw)**
Backup Light	**Backup Light: None**
Lighting Package	**Upfitter Supplied Light Pack**
Lighting Add-Ons	**No Weld-On Light Box**
Rear Facing Rear Bolster Light	**3 Obround Light**
Rear Bolster Marker Lighting	**2.5" Red Marker Light Hole**
Rub Rail Lighting	**No Rub Rail Lighting**
PWS Tanks	**No Prewet Tanks On Body**
Finish Prep	**Wash & Prime Mild Parts Only**
Paint/ Finish	**No Finish**
Asphalt Lip	**8" Pin On 7GA 201 Asp Lip,Inst**
Side Boards	**Mid Point Board Brace Only**
Side Ladder Location	**Ladder/Grabhandle, DS/PS Front Ship Loose**
Side Ladder Type	**Ladder, Pullout 201SS, No Upper**
Body Steps	**4 Sure Step Ship Loose**
Walk Rails	**No Walk Rails**
Vibrator Location	**Vibrator Bracket Between Longsills**
TGS Installation	**No Factory Installed TGS**
TGS Integration	**No TGS Spill Shields**
TGS/Asph Lip Mount Holes	**Mount Holes In Apron and Bolster (Asphalt Lip)**
Special Request	
8" PIN ON 7GA 201 ASP LIP,INST	181573.201 ILO picked

CHASSIS

Chassis Supplier	**Henderson Supplied Chassis**
Order Type	**Turnkey Install**
Cab Type	**Regular Cab**
Chassis Make	**Freightliner**
Chassis Model	**108SD+**
Chassis Model Year	**Model Year 2027**
Hood Type	**Standard OEM Hood Style**
Grille Style	**Stationary Grille**
Hood Snow Door	**No Snow Door On Hood**
Front Frame Extensions	**24" Front Frame Extensions**
Front Frame Wall Type	**Single Wall Front Frame**
Front Frame Wall Thickness	**.44" Frame Rail Wall Thickness**
Front Frame Rail Height	**282.6mm Frame Height**

NASPO ValuePoint SUPPLIER PARTNER
npp gov National Purchasing Partners Government Since 2005

Front Bumper	**OEM Front Bumper Included**
Front Frame Width	**33.62" Frame Width**
Set Back/Forward Axle	**Set Back Axle**
Chassis Axle Quantity	**Tandem Axle**
Front Suspension Load Rating	**15K to 19K Front Suspension**
PTO/Pump Provisions	**Front Mount Pump Provision**
Pump Location	**Front Mount Pump**
Transmission Model	**Allison 3000 Transmission**
Transmission Cooler	**Standard Transmission Cooler**
Backup Alarm	**Chassis Backup Alarm Included**
Battery Box Placement	**Battery Box Under Cab**
Momentary Dash Switch Qty	**No Momentary Dash Switch**
Rocker Switch Qty	**6 Latching Dash Switch**
Plow Light Prep	**Chassis Plow Light Ready**
Beacon/Strobe Prep	**OEM Strobe/Beacon_switch_wiring**
Trailer Plug	**7 Pin Round Plug OEM Installed**
Body builder plug	**Bodybuilder Plug Installed**
Chassis Supplied Camera	**Chassis Supplied Camera**
Chassis Supplied Camera Quantity	**1 Chassis Supplied Camera**
Tow Hooks	**Chassis Supplied Front Tow Hook**
Glad Hands	**Glad Hands Not Included**
Air Line Provision for Glad Hands	**Air Line Provisions Included**
Air Tank Placement	**Under Frame Air Tank**
Fuel Tank Location	**Under Driver Door Fuel Tank**
Fuel Tank Shape	**Round Fuel Tank**
Def Tank Location	**DEF Location Not Specified**
Fuel Tank Size	**70-79 Gallon Fuel Tank Size**
Passenger Seat Style	**Fixed Passenger Seat**
INSTALLATION	
USC Paint Location	**Not Required For Job**
Chassis Delivery To Henderson	**Truck Dealer/Customer Delivers**
USC Build Facility	**USC-MO**
Installation Order Type	**Turnkey Install**
Liquid Type	**Liquid Prep Only**
Spreader Type	**Spreader Prep Only**
Dump Body Type	**Mark E Classic**
Scraper Type	**No Underbody Scraper**
Wing Type	**No Wing Plow**
Front Plow Type	**No Front Plow**
Hitch Type	**Low Profile**
Completed Truck Delivery	**Henderson Delivers (101-160 Miles)**
Hooklift	**No Job Specific Hooklift**
Non-Henderson Equipment	**No Non-Henderson Equipment**
Hitch Mount Style	**Cheek Plate Hitch Mount Kit**
Front Bumper	**Fabricated Channel Bumper, 2 Piece**
Front Tow Hooks	**Tow Hooks, 44K Lb, Pair, USC Supplied**

NASPO ValuePoint SUPPLIER PARTNER

npp gov National Purchasing Partners Government Since 2005

Dump Body Floor Length	**15' Floor Length**
Dump Body Rear Profile	**Straight Tailgate And Apron**
Sideboards	**Sideboards Not Required**
Dump Body Vibrator	**Cougar DC3200, Tandem Axle**
Shovel Holder Quantity	**No Shovel Holders Required**
Ladder 2 Style	**3 Step Pull Out**
Ladder 2 Location	**Passenger Side Front**
Ladder 1 Style	**3 Step Pull Out**
Ladder 1 Location	**Driver Side Front**
Ladder Quantity	**2 Ladders**
Ladder(s)	**Supplied By Factory And Installed At Henderson Upfit**
Grab Handle 2 Type	**Stainless Steel 12" Grab Handle**
Grab Handle 1 Type	**Stainless Steel 12" Grab Handle**
Grab Handle Quanity	**2 Grab Handles**
Grab Handles	**Factory Supplied**
Step 4 Location	**Passenger Side Rear, Outside**
Step 4 Type	**16" Step**
Step 3 Location	**Passenger Side Rear, Outside**
Step 3 Type	**16" Step**
Step 2 Location	**Passenger Side Front, Outside**
Step 2 Type	**16" Step**
Step 1 Location	**Driver Side Front, Outside**
Step 1 Type	**16" Step**
Step Quantity	**4 Dump Body Steps**
Steps	**Factory Supplied And Henderson Upfit Installed Steps**
Asphalt Lip	**Asphalt Lip Supplied & Installed at Factory**
Cabshield Install	**Cabshield Supplied By Factory, Weld To Body At Henderson Upfit**
Pressure Protection Valve	**In Line Air Valve (All Chassis)**
Tailgate Release Type	**Henderson Upfit Supplied Manual Air Over Air Release**
Tailgate Style	**Standard Tailgate**
Dump Body Material	**Stainless Steel Dump Body**
Dump Body Cylinder Type	**Double Acting Hoist Cylinder**
Dump Body Hoist Type	**Telescopic Hoist with Internal Doghouse**
Spreader Tie Down Winch System	**(4) Weld On Spreader Tie Down Winch, Mild (4"x60")**
TGS Spill Shield	**TGS Spill Shield Not Required**
Body Liner	**Body Liner Not Required**
Rubber Mounting Pads	**No Rubber Mounting Pads Required**
Tarp Material	**Black Vinyl Tarp Material Asphalt Rated**
Tarp System Type	**Electric, 30 Deg Arms, With Wind Deflector**
Tarp Brand	**US Tarp System**

NASPO ValuePoint SUPPLIER PARTNER
npp gov National Purchasing Partners Government Since 2005

QD Mount Location Field	**Stainless Steel Quick Disconnect Mount, Front Of Bolster**
Spreader Spinner Install Type	**Standard Spinner Install**
Liquid Drive Configuration	**Hydraulic Drive, Henderson Upfit Installed**
Liquid Controls	**Supplied By Henderson Upfit, Included With Hydraulic Package**
Feedback Sensor	**Supplied By Factory**
Flush Kit	**Flush Kit Not Required**
Liquid Selector Valve Required	**Not Required**
Slurry Tube	**Not Required**
Prewet Discharge Location	**Front Or Rear**
Pintle Plate information	**No Light/Side/Hinge Light, ICC/ 3/4" Combo No Pintle Hook Holes**
Pintle Hook Selection	**Not Required**
Rear Mudflap Mounting	**Swinging Stainless Steel Mount**
Rear Mudflap Material	**Rubber Rear Mudflap With Logo**
Rear Center Mudflap Mounting	**Not Required On Job**
Front Center Mudflap Mounting	**Front Center Mudflap Not Required**
Front Mudflap Mounting	**Frame Mounted Stainless Steel Anti-Sail**
Front Mudflap Material	**Rubber Front Mudflap No Logo**
Poly Fenders	**Not Required**
Pintle Plate	**Pre-Fab Pintle Plate Installed**
Pintle Plate Thickness	**3/4" Pintle Plate Thickness**
Pintle Plate OEM Lights	**No Pintle Plate OEM Lights**
Pintle Plate ICC Lights	**ICC 3 Light Bar**
Pintle Hook Hole Pattern	**No Pintle Hook Holes**
Reflective Tape	**No Logo Reflective Tape 60' Linear**
Lube System	**No Lube System Required**
Miscellaneous D-Ring Quantity	**Not Required**
Exhaust Elbows	**Exhaust Elbow Not Required**
Automatic Tire Chains	**Tire Chains Not Required**
Pusher Axle	**Pusher Axle Not Required**
Toolbox	**Not Required**
Trailer Plug 2	**Not Required For Job**
Trailer Plug 1	**7 Pin Trailer Plug, Round, Aluminum**
Gladhands	**Glad Hands Not Required**
Pintle Plate D-Rings	**Qty 2, 3/4" D-Rings**
Chipper Bar	**Chipper Bar Not Required**
Rear Tow Hook	**44K Lb Pair Installed Rear**
PDP Mount Location	**PDP Mounted On Back Wall**
Misc Electrical Supplies	**Misc Electrical Supplies Required**
GPS System	**GPS System Not Required**
Pavement Temp Sensor	**Not Required**
USC Light Package	**Not Required**
Grille Light(s)	**Grille Lights Not Required**
Camera System	**Camera System Not Required**

NASPO ValuePoint SUPPLIER PARTNER

npp gov National Purchasing Partners Government Since 2005

Wiper(s)	**Wiper Not Required**
Switchbox	**No Switch Box Necessary**
License Plate Lights	**Not Required**
Brake Controller	**Brake Controller Not Required**
Body Up Switch/Light	**Trucklite Body Up Switch/Light**
Back Up Alarm	**Chassis Supplied Alarm**
Roof Beacon Light	**Not Required**
Worklight Quantity	**Not Required**
Roof Spotlight	**Not Required**
Mirrors	**Not Required**
Driving Lights	**Driving Lights Not Required**
Plow Lights Brackets	**Stainless Steel, Freightliner 114SD, Pair**
Plow Lights	**LED, Heated, Trucklite, Rectangular, Pair**
Dump Body Rear Lighting	**3 Each Side**
Dump Body Light Box	**Not Required**
Position 3 from Bottom Strobe Color	**2 Amber Strobes**
Rear Bolster Light Position 3 from Bottom	**Strobe**
Rear Bolster Light Position 2 from Bottom	**Backup**
Rear Bolster Light Position 1 from Bottom	**Stop/Tail/Turn**
Dump Body Side Bolster Lighting	**2.5" Round (Red)**
Dump Body Rub Rail Lighting	**No Rub Rail Lighting**
Cabshield Front Light Quantity	**No Forward Facing Lights**
Cabshield Rear Facing Light Quantity	**No Rear Facing Lights**
Cabshield Side Facing Strobe Color	**Amber 6" Strobes**
Cabshield Side Facing Light QTY	**45 Degree Side Facing Light Pair**
Cabshield Beacon Light	**Cabshield Beacon Light Not Required**
Hydraulic System Source	**Henderson Supplied Hydraulic System**
Hydraulic System Manufacturer	**Certified**
Control Mount Location	**Floor Plate/Pedestal Mount Control**
Hydraulic Control Type	**Electric Controls**
Reservoir Type	**Reservoir Supplied With Hydraulics**
Hydraulic Package	**Full Hydraulic Package**
Quick Coupler Upgrade	**Standard QD Couplers**
Return Filter	**Supplied With Hydraulic Package**
Low Oil Indicator	**Supplied With Hydraulic Package**
High Temperature Oil Shutdown	**Supplied With Hydraulic Package**
Low Oil Shutdown	**Included With Hydraulic Package**
Valve Enclosure Mount Location	**Driver Side Valve enclosure, Frame Mount**
Valve Enclosure Size	**Supplied With Hydraulic Package**
Valve Enclosure Supplier	**Valve Enclosure Supplied w/ Hydraulics**
Stainless Steel Tubing	**SS Lines to Rear of Truck (Standard)**
Body Paint Type	**Natural Finish (SS Only)**
Clear Coat Finish	**No Clear Coat Finish Required**

NASPO ValuePoint SUPPLIER PARTNER

npp gov National Purchasing Partners Government Since 2005

Asphalt Lip Paint Type	**Natural Finish Asphalt Lip (SS Only)**
Undercoat	**No Undercoat Required**
Touch Up Paint	**No Additional Touch Up Paint**
Special Request No Pintle Hook Holes	2.5-inch receiver ILO Picked 22-inches from ground to bottom of receiver
Special Request Hydraulic System Manufacturer: Certified	Certified Quote number 15221835

Single Package Total: $234,658.12

Package Quantity: 1

Total Price: $234,658.12

Due to the volatility in material costs and chassis delays, pricing is subject to change at time of manufacturing and/or upfit.

Henderson offers a deposit program with additional discounts. Please contact your Henderson sales representative for more details.

All terms and conditions apply. Terms of Sale Document available at http://www.hendersonproducts.com/assets/Terms_of_sale.pdf

Signed:_____ **Date:**_____

Quote notes:

Pricing reflects MODOT Contract #IFB605C018000696

NASPO ValuePoint SUPPLIER PARTNER

npp gov National Purchasing Partners Government Since 2005