Drake-Scruggs Equipment Inc

Distributors of Truck and Utility Equipment

Home Office
2000 South Dirksen Parkway
P.O. Box 2549
Springfield, IL 62708-0000
(217) 753-3871
Fax (217) 753-2760

Branch Office
2107 Plaza Drive
Harrisonville, MO 64701-
(816) 925-0929
Fax (816) 925-0936

MODOT / City of Joplin
Attn: Scott Boyer
2309 Barrett Station Rd.
Ballwin, MO 63021-
Tel. (314) 301-1422
Fax

PO

We are pleased to quote to you, the equipment described below delivered F.O.B., Joplin, MO in accordance with specifications attached:

Quote Number **035516-0**
Per the following specification we are quoting:
Install a Versalift SST-37-EIH aerial unit, Knapheide 7132D54RJ service body and accessories installed on a drake-Scruggs supplied 2017 Ram 5500 chassis.

140-4530-530-8220

*** Total ---------- $106,423.00**
Delivery ARO 390 Days

State and municipal sales taxes are to be added if applicable. FET shall be added if applicable.
Terms are Net 10. This Quote is valid for a period of 365 days from Wednesday, December 16, 2015.
Chassis title to be released to customer after full payment for completed unit is received by Drake-Scruggs Equip Inc.
The goods described herein will be sold subject to the additional provisions and our regular warranty printed on the next page hereof. We thank you for the courtesy extended to us, and hope to be favored with your acceptance of this proposal. Your acceptance of this proposal will not be binding upon us until one of our salesmen and an authorizing person of your company approves this proposal hereon in writing. No parts shall be ordered until a signed copy of this form and/or a P.O. has been received.

ACCEPTED:
Date:_____

PO #

Respectfully Submitted,
Drake-Scruggs Equipment Inc.
Quote Prepared By Nathen Barto

* Check mark to receive $700.00 Prepay Chassis Discount. _____.

Firm Name:_____

By:_____ By:_____
Mark Selhime

Drake-Scruggs Equipment Inc.

Distributors of Truck and Utility Equipment

ADDITIONAL PROVISIONS

1. Occasions in which Drake-Scruggs Equipment Inc is to supply the cab and chassis for a customer it shall be invoiced to you upon delivery to Drake-Scruggs Equipment.
2. If, for any reason, delivery is not made within 10 days from the date specified, the cash selling price quoted herein will be subject to adjustment to conform to our regular cash selling price of the goods covered by this proposal in effect at the time of delivery. If the price adjustment results in an increase in price, you shall have the privilege of accepting delivery at the increased price or canceling your acceptance of this proposal by giving written notice of such cancellation to us within 5 days after notice of such price increase is given to you.
3. You agree to accept the goods covered by this proposal, as fulfilled thereof, with such changes in design and materials, or either of them, which we might make.
4. If any sales or excise taxes now in effect, shall be increased, or any new sales, excise, floor or processing taxes shall be imposed by federal, state, or local laws, you are to reimburse us for any and all such increased or new taxes that we may be required to pay or to reimburse to others by reason of the manufacture, purchase or sale of the articles and equipment covered by this proposal. The amount of such increased or new taxes may be billed as a separate item or added to the price of the articles and equipment to which they are applicable at our option.
5. We shall not be responsible for loss, damage, or delays in transportation after shipment, nor for failure to supply any goods covered by this proposal or to deliver the same on time where prevented by strikes, fires, or accidents, or by the demand exceeding the available supply, or by any other cause beyond our reasonable control.
6. Any cost incurred by Drake-Scruggs Equipment, Inc. as a result of either cancellation or change orders shall be passed to the buyer.

*Delivery time is only an estimate. This time may change due to unforeseen problems.

WARRANTY

DRAKE-SCRUGGS EQUIPMENT, INC. Warrants each new article to be free from defects in material and workmanship under normal use and service, its obligation under this warranty being limited to making good any part or parts thereof which shall be returned to it with transportation charges prepaid, and which its examination shall disclose to its satisfaction to have been thus defective, provided that such part or parts shall be so returned to it not later than (90) days after delivery of such article to the original purchaser. This warranty is expressly in lieu of all other warranties expressed or implied and of all other obligations or liabilities on its part, and it neither assumes nor authorizes any other person to assume for it any other liability in connection with the sale of its equipment.

This warranty shall not apply to any article which shall have been repaired or altered outside of its shop in any way so as, in its judgment, to affect its stability, nor which has been subject to misuse, negligence or accident. Warranty on all new equipment is subject to the individual manufacturer as attached.

Your Drake- Scruggs installed equipment is warranted from defects and workmanship for one year from the date of delivery. Included is one free field service trip within this warranty period. Normal travel charges will apply after this initial trip during the one year warranty period. After expiration of the one year warranty, normal travel, labor and material charges will apply. The one year warranty only applies to new components sold and installed by Drake-Scruggs Equipment Inc. Normal maintenance, repairs due to lack of maintenance and equipment transfers from chassis to chassis are not included in this warranty.

Aerial

Versalift SST-37-EIH, insulated, telescopic/articulating, end hung aerial device.
FEATURES:
- Standard platform capacity of 300 LBS
- Platform mounted full pressure Unitrol single-stick control with safety trigger and emergency stop.
- Full pressure turret mounted lower controls including override.
- Engine start / stop from platform and lower controls.
- Continuous rotation
- Three gallon per minute, open center system with an operating pressure of 2250 pounds per square inch.
- Fiberglass inner boom and patented ELECTROGARD provide 42" insulation gap fully retracted, meeting ANSI A92.2-1990 requirements for Category C, 46KV and below.
- ELECTROGARD and inner boom finished with white urethane paint over white gel coat.
- Multi-link hose carrier system through booms is standard with the aerial unit.
- Non-lube bearings used at all pivot points is standard with the aerial unit.
- Integral hydraulic oil reservoir with dual sight gauges and 12 gallon capacity is standard with the aerial unit.
- Master / slave hydraulic leveling with upper control to tilt for cleanout or rescue.
- Molded rubber boom cradle for SST-37 is standard with the aerial unit.
- White urethane paint is standard with the aerial unit.
- Two operators manuals and two service manuals (in English) is standard with the aerial unit.
- Ansi A92.2-1990 data plate is standard with the aerial unti.
- Tubular rubber platform rest for horizontal stowing is standard with the aerial unit.

180 degree platform rotator. (reduces maximum platform capacity by 50lbs.)

Standard full hydraulic controls on the turret.

Hydraulic tool power at upper controls with quick disconnect fittings.

Closed 24" X 30" platform with one step to curbside.

Plastic liner for 24"x30" platform with molded step.

Platform cover, nylon /vinyl 24" X 30"

Continuous boom rotation.

Manlift platform capacity of 400lbs.

Standard chassis pedestal, 47" height.

Emergency 12v DC hydraulic system.

Standard start/stop at the platform and pedestal.

Start/stop located at the tailshelf.

5 pass collector ring assembly.

Chassis insulating system (lower boom insert) providing 12" insulation gap in all positions.

Rubber, tube type platform support

Full body harness and lanyard (xtra large) ARC flash rated.

Aerial painted standard white

H-frame outriggers between the body and cab.

Outrigger boom interlock system for main outriggers.

Manufacturer's recommended amount of hydraulic oil to provide power to the unit.

PTO and gear pump to power aerial hydraulic system.

Body

Knapheide 7132D54 steel service body including the following:
Overall Length: 132" Overall Width: 94"
Pack Depth: 18" Pack Height: 40"

Streetside Compartmentation:
1st Vertical - Three shelves with dividers.
2nd Vertical - Two shelves with dividers.
Horizontal - "Extends to the rear of the body. Side by side pullout drawers with dividers.
Rear Vertical - Short compartment. Open.

Curbside Compartmentation:
1st Vertical - Three shelves with dividers.
2nd Vertical - Two shelves with dividers.
Horizontal - 9 drawer parts cabinet in the front, one shelf in the rear.
Rear Vertical - Three shelves with dividers.

Additional Features:
- Drop in tailboard at the rear of the cargo area.
- Painted white to match the chassis.
- Compartment interiors painted white.
- Master lock system.
- 24" steel treadplate tailshelf with underbody step and grab handle curbside.
- LED stop/tail/turn and back up lights recessed into the tailshelf.
- Four (4) D-ring tie downs on the cargo floor. Location to be determined at time of order.

Mudflaps installed per state and federal regulations.

Underbody cable step curbside under the tailshelf.

Pool style grab handle curbside of the tailshelf.

Safety Equipment

Ecco SA901 back up alarm.

Triangle reflector kit. Shipped loose.

5 LB - ABC rated, fire extinguisher mounted in the cab if there is no interference.

Two (2) rubber wheel chocks 10" L X 8"D X 5" H with handle

Two (2) Dica model D1818 outrigger pads.

Large ball stainless steel grounding lug mounted at the rear.

Towing Equipment

Acme ICC bumper with pintle plate. Includes D-ring each side and 2"x2" receiver tube. Painted black.

Chassis frame reinforcement for pintle hitch.

Buyers BH-82000, 8 ton combination pintle hitch with 2 inch ball

Pollack 7 spade car end socket. (Plug will be wired to industry standard unless otherwise requested by customer)

Dodge Option

2017 Ram cab chassis. See attached spec.

Certification

Unit certification. Includes dielectric test, stability test, clean and weigh prior to pick up or delivery.

Option 5

4 axis right hand control in lieu of the standard 3 axis controller.

Option 6

Lift eye on outer boom with 500lb capacity.

Option 7

24" X 30" end hung, walk-in platform open to the curbside. Inlcudes left hinged door.

Option 9

120v hydraulic tank heater. Plug location to be determined at pre-paint inspection.

Option 10

Magnum Energy MS2000 pure sinewave inverter. 2000 watt inverter. Location to be determined at pre-paint inspection. Wired to the chassis battery/batteries. Does not include additional batteries.

Option 13

Rear underframe torsion bar and front Timbren load boosters in lieu of the quoted outriggers.

Option 17

TruGuard dielectric isolating system with right hand single stick control. All control handles are isolated and tested per ANSI 92.2 2009. the high resistive dielectric system is protected from direct environmental and job related contamination. TruGuard technology incorporates the use of full hydraulic controls with durable metal handles and linkages.

Option 18

Electroguard. Provides 42" insulation gap fully retracted.

Optional Aerial

Versalift SST-40-EIH, Insulated, end mounted 40' telescopic /articulating aerial platform lift in lieu of the quoted SST-37-EIH.

Warranty Option 2

2 year Extended Warranty

Additional added options

LED Rope lighting top and sides of each compartment. Wired to a switch in the cab.

Ecco model 3455A Signal Bar Kit: LED Safety Director, 9 flash patterns, in-cab controller, 55' cable, LED, 12VDC, amber. Mounted at the rear under the tailshelf.

Six (6) Ecco Model ED3766AC Directional LEDS: Dual color, surface mount 12-24 VDC 12 flash patterns. Amber/clear. Mounted two facing the front on the grill, two facing the rear on the tailshelf and one each side of the body. Wired to a single switch in the cab.

Total for One Unit	**$64,935.00**
Chassis Price	**$41,488.00**
Grand Total	**$106,423.00**

If chassis is paid for at the time of delivery to Drake-Scruggs Equipment Inc., deduct $700.00 from the above total price. *Title will be held until unit is paid in full*

FOB: **Joplin, MO**
State and municipal sales taxes are to be added if applicable.
FET shall be added if applicable.

Replace 1646 Boom Truck