Vacation of Streets or Easements Application

Return Form to:
Planner
Joplin City Hall
602 S. Main Street
Joplin, Missouri 64801
417-624-0820 Ext. 1511
Zoning-Planning@JoplinMO.org

Office Use Only
Case No.: 025-24
Filing Fee: $600.00
Received: 5/20/24
Date Advertised: _____
Proj. No.: 24-089
Public Hearing Date: 6/10/24

Applicant: First Street Development, LLC. Phone No.: 314.566.8026

Address: 4700 Belleview Ave, Suite 415, Kansas City, MO 64112 Email: andy@firststreetdev.com

Owner: Seneca Enterprises MO, LLC Phone No.: 615.545.6837

Address: 3017 Abigail St., Joplin, MO 64804 Email: ashokpatelabc@gmail.com

Location of Street or Easement: THE NORTH-SOUTH 20 FOOT ALLEY LOCATED BETWEEN LOTS 7-8 AND LOTS 9-10 OF CAMPBELL'S FIRST ADDITION TO JOPLIN, JASPER COUNTY, MISSOURI.

Type of Vacation: Street Easement (Alley) Plat

RIGHT OF WAY VACATION ONLY | UTILITIES & UTILITY EASEMENT TO REMAIN

Instructions: Please indicate below the extent to which the following standards are met, in the applicant's opinion.

Yes	No	
☒	☐	Private rights will not be injured or endangered by the vacation.
☒	☐	The vacation will not cause the public to suffer a loss or inconvenience.
☒	☐	In justice to the applicant(s) the vacation should be granted.

Submission of Documents: The following documents are **required** at time of submission.

Yes	No	
☒	☐	Legal description of the street, alley, or utility easement to be vacated from a deed of record or certified survey. Digital copies are acceptable. Must be legible.
☒	☐	Survey or such other drawing acceptable to the Director of Planning,

Vacation of Streets or Easements Procedures

Applicability. Vacation is the process to eliminate any plat, part of a plat, street, alley, utility easement, or public reservation of land. The application shall be made by the public entity owning the property interest in the property sought to be vacated or by all owners of lands adjoining on both sides of the street, alley or public reservation proposed to be vacated.

Review Criteria. A vacation shall be reviewed according to the following criteria:

1. The application is in accordance with the comprehensive plan. In particular, the impact of the vacation on physical patterns, arrangement of streets, blocks, lots and open spaces, and public realm investments reflect the principles and concepts of the plan.
2. Compliance with the requirements of this code. In particular, the vacation is consistent with the intent and design objectives of the subdivision design standards.
3. The vacation reflects sound planning and urban design principles with respect to existing and potential development in the vicinity, including consideration of current and future streets, opens spaces, blocks, lots, and public utilities and facilities.
4. Any impacts identified by specific studies or technical reports are mitigated with generally accepted sound planning, engineering, and urban design solutions, that reflect long-term solutions and sound fiscal investments.
5. No private rights will be injured or endangered by the vacation.
6. The street, easement or other public reservation of land to be vacated no longer serves a public purpose.
7. All resulting lots and parcels are capable of meeting the intent and objectives of the applicable zoning districts and development standards.

Review Procedures. In addition to the general requirements in Table 2-1 and Section 2.01, the following requirements are specific to vacations:

1. Notice shall be published for two consecutive weeks in an official City newspaper. The notice shall state that an application for vacation has been filed in the office of the City Clerk, describing the property fully, and including all other information required for public hearings in Section 2.01.
2. The City Council or the Director may determine that it would be advisable to obtain the recommendation of Planning Commission concerning a vacation application prior to the public hearing before the City Council. In that event, the Planning Commission shall hold its own public hearing on the application according to the same procedures as City Council. At the conclusion of any such hearing, the Planning Commission shall submit its recommendation on the application to the City Council.
3. Approval of a vacation shall be by ordinance adopted by the City Council.

Effect of Decision. The vacation shall be effective on the date specified in the ordinance and after recording with the applicable county Recorder of Deeds. In approving a vacation, the City Council may place any conditions it deems necessary to protect the public health, safety and welfare, including the requirement for easements. The Director shall certify to the City Clerk when any conditions have been met and, upon such certification, the vacation may be recorded.

Development, & Neighborhood Services depicting the street, alley or public reservation sought to be vacated and the properties and property ownerships surrounding said street, alley, or public reservation.

☒ ☐ Affidavit(s) from each owner of land adjoining said area that is proposed to be vacated, who are not listed as an applicant, indicating their consent to the vacation.


☐ ☒ Completed Utility Comments forms from the following utility companies indicating their consent to vacate the easement. The following companies must be contacted, and their consent received, before the Public Hearing can take place.

RIGHT OF WAY VACATION ONLY | UTILITIES & UTILITY EASEMENT TO REMAIN

Utility	Contact	Email	Phone
AT&T	Gene Lollis	IL0967@att.com	417-499-7819
MoAm Water*	Derec Bass	derec.bass@amwater.com	
MoAm Water*	Trenton Mccarty	trenton.mccarty@amwater.com	
MoAm Water*	Bob Kirby	bob.kirby@amwater.com	
Liberty Utilities (Power)	Jeff Lebeda	jeff.lebeda@libertyutilities.com	417-625-6159
Republic Services (Trash)			(800) 431-1507
Cable One/Sparklight	Keri Bledsoe	keri.bledsoe@sparklight.biz	
Spire Energy (Gas)**	Ken Stegall	ken.stegall@spireenergy.com	
Spire Energy (Gas)**	Mandy Butkovich	mandy.butkovich@spireenergy.com	816-472-3767
City Sanitary Sewer	Chris Parker	cparker@joplinmo.org	417-624-0820 x1584
City Stormwater	Steven Martinez	smartine@joplinmo.org	417-624-0820 x1531

*Must contact ALL contacts at MoAm Water.
**Must contact BOTH contacts at Spire Energy.

Signature: _____ **Date:** 5/20/2024



HATCH LEGEND

- STANDARD DUTY ASPHALT PAVEMENT
- STANDARD DUTY CONCRETE PAVEMENT
- HEAVY DUTY CONCRETE PAVEMENT
- CONCRETE SIDEWALK PAVEMENT

SITE DATA

ZONING- C-3

TOTAL PROPERTY AREA	0.704 ACRES
DISTURBED AREA	X.XX ACRES

BUILDING DATA

BUILDING GROSS SF	APPROX950 SQ FEET

PARKING DATA

CITY REQUIREMENT - RESTAURANT -1 PER 3 SEATS
(OUTSIDE SEATING EXCLUDED)

REQUIRED PARKING	0
PROVIDED PARKING	12
ADA ACCESSIBLE REQUIRED	1
ADA ACCESSIBLE PROVIDED	1

LEGAL DESCRIPTION

ALL OF LOTS NUMBERED SEVEN (7) AND EIGHT (8), EXCEPT THE EAST 15.00 FEET TAKEN FOR ROAD RIGHT OF WAY OF LOTS NUMBERED NINE (9) AND TEN (10), ALL IN CAMPBELL'S FIRST ADDITION TO JOPLIN, JASPER COUNTY, MISSOURI

PARCEL NUMBER

19101210010013001
19101210010011000

OWNER INFORMATION

SENECA ENTERPRISES MO
1032 S RANGELINE

NAME
NUMBER

CLIENT

ENGINEERING FIRM OF RECORD

aubry enterprises.

KANSAS OFFICE
15195 METCALF AVE UNIT A
OVERLAND PARK, KS 66223

COLORADO OFFICE
48700 COUNTY RD FF
AKRON, COLORADO 80720

REV	DESCRIPTION	DATE

###########

4/1/2024


###############

###########

###############

#########

#####



0 30 60

SCALE: 1" = 30'

* No corner monuments were set on Easement (Per request)

* Right-of-Way acquired by MoDOT on the East side of Lots 7 & 8 acquired an additional 15' (including the original 30 feet from plat)

SURVEYOR'S CERTIFICATION

I, William A. Booe, a duly licensed Land Surveyor in the State of Missouri, do hereby certify that this plat was prepared from the notes of an actual on the ground field survey done by me or under my direct supervision on April 19, 2024 and that the information shown hereon is true and correct and meets or exceeds current Missouri Minimum Standards for Boundary Surveys.

STATE OF MISSOURI
WILLIAM A. BOOE
NUMBER PLS-2002010970
PROFESSIONAL LAND SURVEYOR
5-20-24

William A. Booe, PS 2002010970
w.booe@cornerstone-rs.com

LEGEND

- Existing Iron Rod Origin Uncertain (unless noted)
- Set 1/2"x24" Iron Rod with 1.5" Plastic Yellow Cornerstone Cap Stamped LS110 (unless noted)
- Boundary Line
- Easement Line
- (M) Measured Dimension
- (D) Deed Dimension
- (P) Plat Dimension

PROPOSED EASEMENT DESCRIPTIONS & VACATION

PROPOSED ALLEY VACATION AND CONVERTED TO A UTILITY EASEMENT
(WRITTEN BY WILLIAM A. BOOE, LS 2002010970, DATED MAY 17, 2024):

THE NORTH-SOUTH 20 FOOT ALLEY LOCATED BETWEEN LOTS 7-8 AND LOTS 9-10 OF CAMPBELL'S FIRST ADDITION TO JOPLIN, JASPER COUNTY, MISSOURI.

PROPOSED ACCESS EASEMENT
(WRITTEN BY WILLIAM A. BOOE, LS 2002010970, DATED MAY 17, 2024):

A TRACT OF LAND LOCATED IN A PORTION OF LOT 7 AND LOT 10 AND THE ADJACENT ALLEY IN CAMPBELL'S FIRST ADDITION TO JOPLIN, JASPER COUNTY, MISSOURI, MORE PARTICULARLY DESCRIBED AS FOLLOWS: COMMENCING AT THE NORTHWEST CORNER OF SAID LOT 10, THENCE S 01°59'40" W, ALONG THE WEST LINE OF SAID LOT 10, 9.54 FEET TO THE POINT OF BEGINNING; THENCE S 88°05'40" E, BEING PARALLEL TO THE NORTH LINE OF SAID LOT 10, 128.17 FEET; THENCE N 1°59'40" E, 9.54 FEET TO A POINT ON THE NORTH LINE OF SAID LOT 10 AND BEING 1.94' WEST OF THE NORTHEAST CORNER OF LOT 10; THENCE S 87°58'41" E, 24.00 FEET TO A POINT LYING 1.94 FEET EAST OF THE NORTHWEST CORNER OF LOT 7 OF SAID CAMPBELL'S FIRST ADDITION TO JOPLIN; THENCE S 01°59'40" W, 33.55 FEET TO A POINT LYING 1.92 FEET EAST OF THE WEST LINE OF SAID LOT 7; THENCE N 88°05'40" W, BEING PARALLEL WITH THE NORTH LINE OF LOT 10, 152.17 FEET TO A POINT ON THE WEST LINE OF SAID LOT 10; THENCE N 01°59'40" E, ALONG THE WEST LINE OF SAID LOT 10, 24.00 FEET TO THE POINT OF BEGINNING CONTAINING 3880 SQUARE FEET, MORE OR LESS.

EASEMENT DESCRIPTIONS / ALLEY VACATION
A PORTION OF LOTS 7 & 10,
CAMPBELL'S 1ST ADDITION
To The CITY of JOPLIN, JASPER COUNTY, MO.

DRAWN BY: RRZ	DATE: 5-17-2024	JOB NO. 1-24020053M ESMT	
CHECKED BY: WAB	REVISION DATE: 5-20-2024	REF. JOB NO. N/A	
PREPARED FOR: FIRST STREET DEVELOPMENT			

CORNERSTONE Regional Surveying, LLC
Serving Kansas, Missouri & Oklahoma
617 S. Hwy 69 Pittsburg, KS 66762 Ph: 620-235-1166