SPRINGFIELD SIGN

SPRINGFIELDSIGN

Date 7/19/2024
Estimate # 101

Springfield Sign

4825 E Kearney St
Springfield, MO 65803
Phone: 800-845-9927

Change Order #1

Project #3
City Wayfinding
Joplin, MO

Building Images That Build Business

#	QTY	Product or Service	Unit Price	Total
1	19	40" x 32" .125 aluminum, single sided sign panels with retroreflective vinyl graphics per city design. *3 signs are double sided (two panels each).	$215.00	$4,085.00
2	19	12' (10' overall mounting height) 2 3/8" round black (powder coated) 16 gauge galvanized steel posts.	$185.00	$3,515.00
	19	2 3/8" round galvanized steel post caps powder coated black.	$10.00	$190.00
3	32	Sets of black (powder coated) galvanized steel hardware brackets for single sided signs	$19.95	$638.40
4	6	Sets of black (powder coated) galvanized steel hardware brackets for double sided signs	$24.50	$147.00
5	19	**ADD:** Paint the backs of the panels matte black	$26.73	$507.87
6	1	5 year product warranty		
7	1	Complete in 25 business days		
8				
9				
10				
11				

NEW ADDITION (GRAND FALLS WAYFINDING)
Metal fabrication with the new design (city to provide artwork), vinyl; to include installation -- to include posts and hardware. Project #3 equals 19 signs at 16 sign locations, with three double-sided. City to provide locations and setbacks for new signs. Tax exempt.

Product Total:	$9,083.27
Survey/Marking:	$500.00
Setting Footings:	$3,500.00
Installation:	$3,760.00
Installation Total:	$7,760.00
Total:	$16,843.27

Customer Name:_____ Company:_____

Customer Signature:_____ Date:_____

Thank you for choosing Springfield Sign! We appreciate the opportunity to serve you. If you have any questions, please contact Mike Dardis at 208.738.6062 or michaeld@springfieldsign.com