CITY OF JOPLIN MISSOURI

ADDENDUM No. 3

Issued to all Bid Document Holders of Record.

Date: July 14th, 2021

Project Name: 10th and Main Culvert Replacement

*****When submitting bid, Contractor must execute and submit a copy of all issued Addendum as well as Addendum No.3 proposal included in this addendum along with an executed acknowledgement of receipt of addendum form. A bid bond must also be submitted with a bid. *****

## Proposal Changes

The following modifications were made to the proposal.

- Quantity for Line item #15 "Concrete Pavement Repair" has been increased from 30 SY to 40 SY.

## Job Special Provisions (JSP) Addition

- Railroad to provide one week of flagging services at no cost. Contractor shall complete all work requiring railroad flagging services within one week. Any work requiring railroad flagging services done exceeding the 1-week threshold shall be done so at contractor's expense for flaggers. City will not provide reimbursement for railroad flagging services.

- 9' x 9' junction box may be pre-cast or cast in place. At contractors option a pre-cast box with no lid may also be used and the lid may be cast in place. Reinforcement for cast-in place options shall be in accordance with sheet number 7 of section 703.17 of MODOT's 2021 Missouri Standard Plans for Highway construction using a design fill of 2 feet for a span of 9 feet and height of 9 feet. If a pre-cast box with cast in place lid option is chosen, the cast in place lid shall be 12 inches thick with reinforcement in accordance with sheet number 7 of section 703.17 of MODOT's 2021 Missouri Standard Plans for Highway construction using a design fill of 2 feet for a span of 9 feet and height of 9 feet. Further, if a combination pre-cast box with cast in place lid option is chosen, contractor shall include the cost of both within line item # 19 (9' x 9' Junction Box). No additional payment shall be made for cast in place lid.

# City of Joplin
# 10th and Main Culvert Replacement
# Addendum No. 3
# Questions and Answers Received by 7/14/2021

The following clarifications shall be utilized for preparing bids.

1. Can you tell me who will need to knock down the EPA waste area?
    a. Should there be any contaminated material taken offsite for disposal at the EPA or City waste area the contractor will not be required to knock down the piles of waste. This will be handled by either the EPA or City personnel.
2. Can you tell me the location of the Single Type A catch basin?
    a. Single Type A catch basin has been removed from the proposal. All catch basin installations are Type C Inlets and are noted on the plans.
3. What is the pay item for the 18" VCP stacked x 2 to the new junction box on 10th street?
    a. Connections of existing storm sewer pipes to the new junction box shall be included in the price of the new junction box. No additional payment will be made for connections of existing storm sewer pipe to the new junction box.
4. Is the 30 SY of concrete pavement repair for the over excavation at the 9' x 9' junction box?
    a. The 30 SY of concrete pavement repair was included for the curb and gutter installation. Quantity of concrete pavement repair has been increased in proposal to account for over excavation for junction box.
5. Can you tell me if the concrete pavement repair will need to be black concrete?
    a. Concrete pavement repair **will not** be required to be black concrete.
6. Could you tell me if the 9' x 9' junction box could possibly be pre-cast, or were your plans to have this cast in place?
    a. 9' x 9' junction box may be pre-cast or cast in place. At contractors option a pre-cast box with no lid may also be used and the lid may be cast in place. Reinforcement for cast-in place options shall be in accordance with sheet number 7 of section 703.17 of MODOT's 2021 Missouri Standard Plans for Highway construction using a design fill of 2 feet for a span of 9 feet and height of 9 feet. If a pre-cast box with cast in place lid option is chosen, the cast in place lid shall be 12 inches thick with reinforcement in accordance with sheet number 7 of section 703.17 of MODOT's 2021 Missouri Standard Plans for Highway construction using a design fill of 2 feet for a span of 9 feet and height of 9 feet. Further, if a combination pre-cast box with cast in place lid option is chosen, contractor shall include the cost of both within line item # 19 (9' x 9' Junction Box). No additional payment shall be made for cast in place lid.

7. Will MNA railroad require permit fees and flaggers for the project?
    a. Contractor will be required to acquire a right of entry permit from the railroad for which the railroad has waived fees for. Contractor will also be required to carry railroad insurance per the requirements for the right of entry permit. Railroad to provide one week of flagging services at no cost. Contractor shall complete all work requiring railroad flagging services within one week. Any work requiring railroad flagging services done exceeding the 1-week threshold shall be done so at contractor's expense for flaggers. City will not provide reimbursement for railroad flagging services.
8. Will the contractor be required to handle any pull box and/or traffic signal adjustments?
    a. No. City will arrange to have any necessary pull box and/or traffic signal adjustment work related to this project completed by means of a separate contractor outside of this contract.

This addendum forms a part of the contract described above. The original Contract Documents and any prior addenda remain in full force and effect as modified by the following that shall take precedence over any contrary provisions in the prior documents.

David K. Hertzberg, PE
Director of Public Works

7/14/2021
Date

***Each bidder shall acknowledge receipt of this addendum by affixing his signature below by noting this addendum on his bid form, and by attaching this addendum to his bid.***

**ACKNOWLEDGEMENT**

The undersigned acknowledges receipt of this addendum and the Bid submitted in accordance with information, instructions and stipulations set forth herein.

Bidder:_____

Signed By: _____

Date: .....

# ADDENDUM #3 PROPOSAL

THE UNDERSIGNED hereby proposes to furnish the labor and material for:

**Project: 10th and Main Culvert Replacement**

in the City of Joplin, Missouri, according to Drawings, Contract Documents and General Specifications for such work on file in the office of the City Engineer and Director of Public Works, together with the terms and conditions to be stipulated in the general contract forms, now adopted by the City of Joplin, as advertised to be let on July 20, 2021 at the following prices to- wit:

| 10th and Main Culvert Replacement | | | | | |
|---|---|---|---|---|---|
| **Item No.** | **No. of Units** | **Unit** | **Description** | **Unit Price** | **Extended Price** |
| 1 | 1 | LS | Erosion Control, TEMP | | |
| 2 | 1 | LS | Topsoil, Seeding, Mulching and Fertilizing | | |
| 3 | 1 | LS | Mobilization (not to exceed 5% of total bid) | | |
| 4 | 1 | LS | Removal of existing improvements | | |
| 5 | 1 | LS | Earthwork (Unclassified Excavation and Embankment) | | |
| 6 | 20 | LF | Remove and Replace fence | | |
| 7 | 11 | LF | Handrail | | |
| 8 | 1 | EA | Concrete Washout Basin | | |
| **Excavation** | | | | | |
| 9 | 100 | CY | Transportation and disposal of contaminated material | | |
| 10 | 250 | CY | Imported Fill | | |
| **Concrete Structures** | | | | | |
| 11 | 228 | LF | Curb and Gutter (Includes 4" stone base) | | |
| 12 | 256 | SY | 6" thick concrete sidewalk (includes 6" stone base) | | |
| 13 | 42 | SY | Commercial Concrete Driveway, 6" Thick | | |

| | | | | | |
|---|---|---|---|---|---|
| 14 | 40 | SY | 'Type C" ADA Ramp (includes truncated domes) | | |
| 15 | 40 | SY | Concrete Pavement Repair | | |
| **Storm Sewer Installation** | | | | | |
| 16 | 173 | LF | 72" Class III RCP (includes bedding, cover and trenching) | | |
| 17 | 28 | LF | 15" RCP, (includes bedding, cover, and trenching) | | |
| 18 | 1 | LS | 12" Headwall for 72" RCP (including 8" Concrete slab apron and 8" Wing Walls) | | |
| 19 | 1 | EA | 9' x 9' Junction Box | | |
| 20 | 3 | EA | Type C Inlet | | |
| **Traffic Control** | | | | | |
| 21 | 2 | EA | W020-1 (Road Construction ahead sign) | | |
| 22 | 2 | EA | WO20-2 (Detour Ahead sign) | | |
| 23 | 1 | EA | WO1-4L | | |
| 24 | 2 | EA | 2-R11-2 (Road Closed Sign) | | |
| 25 | 2 | EA | R3-1 (No right tum sign) | | |
| 26 | 2 | EA | R3-2 (No left turn sign) | | |
| 27 | 3 | EA | M4-9 (Detour right sign) | | |
| 28 | 2 | EA | M4-10 (Detour left sign) | | |
| 29 | 2 | EA | C14 (End Road Work Sign) | | |
| 30 | 1 | EA | C16 (One Lane Road Ahead Sign) | | |
| 31 | 2 | EA | C23 (Road Work Ahead Sign) | | |
| 32 | 2 | EA | Sidewalk Closed Sign (On Barricade) | | |
| 33 | 2 | EA | Sidewalk Closed Use Other Side Sign | | |
| 34 | 4 | EA | Changeable Message Board (90 days) | | |
| 35 | 21 | EA | Channelizers | | |
| 36 | 10 | EA | Type III Barricades | | |
| | | | | **Total Base Bid** | |

BIDDER understands that they may be asked to provide a complete and detailed breakdown of bid item prices following opening of the bids but prior to award of contract. BIDDER also hereby certifies that the bid prices for each component of the project will be substantiated by submittal of a detailed cost breakdown of all components of the PROJECT to the ENGINEER prior to release of any payments to the BIDDER for work performed.

BIDDER understands and acknowledges that the bid items shown in this proposal represent a summary of major components of construction required. The bid price for each item shall include the cost of all adjacent or related items that are shown on the plans, are called for in the specifications, or are otherwise necessary to provide completely the improvements.

BIDDER agrees that this bid shall be good and may not be withdrawn for a period of ninety (90) consecutive calendar days after the scheduled closing time for receiving bids.

BIDDER understands that the City has the right to waive any informalities and maintains the right to reject any or all bids.

The undersigned agrees to enter into a contract within seven (7) days from notice of award should this proposal be accepted, and enter into bonds with good and sufficient securities, to complete the work on or before a date to be specified in the Notice to Proceed, and to fully complete the project within 90 consecutive calendar days thereafter. A penalty of $500.00 per calendar day thereafter shall be instituted, the amount to be deducted from the contract price. In order to pay all labor employed and material used in connection with this work and to adjust all claims or liens that may arise in consequence of said work, to the satisfaction of the Director of Public Works, above said bonds shall also indemnify and save harmless the said City from all damages or injuries to any person or persons, either in the employ of the contractor, his agents, servants or employees. In the event of the failure of the undersigned to enter into such contract within seven (7) days of the award, then the deposit of five percent (5%) of the total bid amount as surety is therefore forfeited to the City of Joplin.

All applicable laws, ordinances, and the rules and regulations of all authorities having jurisdiction over construction of the PROJECT shall apply to the Contract throughout.

Each BIDDER is responsible for inspecting the site and for reading and being thoroughly familiar with the CONTRACT DOCUMENTS. The failure or omission of any BIDDER to do any of the foregoing shall in no way relieve any BIDDER from the any obligation in respect to his BID.

The low BIDDER shall supply the names and addresses of the major material SUPPLIERS AND SUBCONTRACTORS when requested to do so by the OWNER.

Dated____ day of__________________ 20

Company ______________________________

Address ______________________________

Signature ______________________________

(Print Name) ______________________________