June 10, 2021

CITY OF JOPLIN
32ND STREET WIDENING
CENTRAL CITY RD TO SCHIFFERDECKER AVE

Addendum No. 4

Contract Bidders:

Enclosed is Addendum No. 4 for the above referenced project. Please execute, attach, and submit this Addendum No. 4 with your bid.

Olsson




Brian Coomes, P.E.

Project Engineer

CITY OF JOPLIN
32ND STREET WIDENING
CENTRAL CITY RD TO SCHIFFERDECKER AVE

**ADDENDUM NO. 4**

**CLARIFICATIONS**

1. Refer to Bid Items 130, 1003, & 2005.

   Contractor shall furnish and install steel casing as discussed in Addendum 2, Items 6 & 8. Contractor shall be responsible for furnishing all accessories for a complete casing installation, including but not limited to casing spacers, end seals, vents, and other items. These shall be considered subsidiary to the corresponding casing bid item.

2. Refer to Bid Items 1001, 1002, 1004, 1005, 1006, 1007, 1011, 2001, 2002, 2003, 2004, 2007, 2008, 2009, 2010, 2011, 2012, & 2015.

   Missouri American Water Company will furnish waterline materials as discussed in Addendum 2, Item 6. More specifically, Missouri American Water Company will furnish all pipe materials (including restrained joint ductile iron – TR Flex Locking, PVC, and PE), ductile iron pipe fittings, valves, tapping sleeves, fire hydrant assemblies, tracer wire, test stations, and ductile iron pipe wrap. Contractor shall be responsible for all excavation, bedding, backfill, installation, testing, and all other incidentals required for a complete and functioning water system in accordance with the plans & specifications.

3. Refer to Bid Item 2006.

   Contractor shall furnish all materials, equipment, and incidentals required for a complete installation of the Hydro-Stop Line Stop. Missouri American Water Company will not furnish any materials required for this line item.

4. Regarding Expansion Joints in Sidewalk, Driveways, and Concrete Pavement.

   All sidewalk expansion joints, driveway expansion joints, and expansion joints in concrete pavement shall be sealed in accordance with Section 3100.3.20 of the City of Joplin Specifications. This work shall be considered subsidiary to the respective concrete bid item.

5. Refer to Bid Item 103.

   Permanent Signage sizes shall be provided per MUTCD standard minimum size for a conventional multi-lane roadway.

The undersigned hereby acknowledges receipt of this addendum, which by this reference is hereby incorporated in and becomes a part of the Contract Documents for the above referenced project. **PLEASE ATTACH THIS ADDENDUM TO YOUR BID.**




_____
Company Name

_____
Signature

_____
Printed Name

_____
Title

_____
Address

_____
City/State/Zip

_____
Telephone Number