ADDENDUM TO #2022-RFP-15

In #2022-RFP-15, issued Thursday, June 16, 2022 under Scope of Work replace the 4th instruction: "Roofing Contractor shall have 30 calendar days for completion of this project after Notice to Proceed, with a $100.00 per day deduction for each working day over finish date. Rain days excluded. "

With the following:

"Due to the potential difficulty in obtaining materials, the Roofing Contractor shall have 30 calendar days for completion of this project after contractor receives materials, with a $100.00 per day deduction for each working day over finish date. Rain days excluded."

In #2022-RFP-15, issued Thursday, June 16, 2022 on page 4 under general description and specifications lines 2 and 4 should be ignored and replaced with the following:

2. Remove existing roofing and fiber board down to steel roof deck and install ¼ inch per foot tapered insulation.

4. This includes installing 2 drains in the North West section of the roof.