CITY OF JOPLIN
ADDENDUM NUMBER 1

Issued to all Bid Document Holders of Record.

Date: 3/28/2024

Project Name: 4th Street & Murphy Blvd. Geometric Improvements

This addendum forms a part of the contract described above. The original Contract Documents and any prior addenda remain in full force and effect as modified by the following that shall take precedence over any contrary provisions in the prior documents. The following clarifications are made:

Clarifications

1. **Traffic Control:** Traffic control will not require a signed detour route.
    a. Contractor to install two dynamic message boards set at the intersections of Murphy Boulevard and Main Street and Murphy Boulevard and 7th Street (set such to not encroach on MoDOT right-of-way).
    b. Install two Type III barricades at the intersection of Murphy Boulevard and Pool Street during Phase IV.
    c. Larger 48" signage will be allowed.
2. **Signal/Electrical:**
    a. SDR9 to be used for signal conduit. Other conduits may be other material.
    b. Contractor may splice conduit by the following methods:
    1. Fusion Welded will be required under pavement.
    2. Shurlock coupler may be used in other locations.
    c. Pull box 1 near the underpass may be the same style pull box as pull boxes 1-6. Pull box 1 shall be included in alternate 3 bid price.
3. **Inspection & Testing:** The City of Joplin will provide inspection and testing for the project
4. **Permits:** Contractor will be responsible to obtain all applicable permits associated with parking lot and lighting/signal construction.
5. **Park Signage:**
    a. The contractor shall submit shop drawings for review for the Landreth Park and J signs. The shop drawings shall include the location of the electrical connections.
    b. The detail in the plans indicates a penetration through the wall to mount a box on the back side of the wall and routing of the conduit along the back of the wall to prevent any of the vertical leg of conduit being visible from the front of the wall.
    c. The electrical for the signs should be included in the respective bid items in Alternate 1.
    d. The LED tape light that is part of the signage may be included in either the signage scope or the electrical contractor's scope at the discretion of the bidder.
6. **Contractor Completion Time:**
    a. The contractor shall be given an early notice to proceed that provides additional time for ordering and procuring materials. Contractor shall have 90 days to complete construction once construction activities begin; final completion date shall be on or before November 27, 2024.

Last Day for Questions: Due to issuance of addendum 1, questions can be submitted through 12:00 PM (Noon) Friday, March 29th.

In order to have a valid bid proposal, this addendum must be acknowledged and returned with your bid proposal.

If you have any questions concerning this addendum, please feel free to contact Jonathan Peitz at (417) 885-1763.

Daniel Johnson, PE
Director of Public Works

3-28-24
Date

Each bidder shall acknowledge receipt of this addendum by affixing his signature below by noting this addendum on his bid form, and by attaching this addendum to his bid.

ACKNOWLEDGEMENT

The undersigned acknowledges receipt of this addendum and the Bid submitted in accordance with information, instructions and stipulations set forth herein.

Bidder: _____

Signed By: _____

Date: _____