ADDENDUM No. 1

Issued to all Bid Document Holders of Record.

Date: June 27th, 2025

Project Name: Justice Center Sidewalks 2025

When submitting bid, Contractor must execute and submit a copy of all issued Addendum as well as Addendum No.1 proposal included in this addendum changes to original proposal are in red. Also attached is an acknowledgement of receipt of addendum form

PROPOSAL

THE UNDERSIGNED hereby proposes to furnish the labor and material for:

Project: JUSTICE CENTER SIDEWALKS 2025

in the City of Joplin, Missouri, according to Drawings, Contract Documents and General Specifications for such work on file in the office of the City Engineer and Director of Public Works, together with the terms and conditions to be stipulated in the general contract forms, now adopted by the City of Joplin, as advertised to be let on July 9, 2025 at the following prices to-wit:

Base Bid					
Item No.	Description	Quantity	Unit	Unit Price	Extended Total
1	6" FIBER REINFORCED SIDEWALK	710	SY		
2	ADA RAMPS	73	SY		
3	STANDARD CURB AND GUTTER	128	LF		
4	8" FIBER REINFORCED CONCRETE PVMT. REPAIR	65	SY		
5	REMOVAL OF EXIST. IMPROVEMENTS	775	SY		
6	BLACK DIRT SEED AND MULCH	652	SY		
7	TRAFFIC CONTROL	1	LS		
8	4” TRAFFIC YELLOW STRIPING	152	LF		
9	PAINT CURB TRAFFIC RED	107	LF		
10	PAINT CURB TRAFFIC YELLOW	347	LF		
11	SIGN RELOCATION	1	EA		
12	TREE STUMP GRINDING	11	EA		
13	TREE REMOVAL	1	EA		
14	SIDEWALK TRENCH DRAIN REPLACEMENT	1	EA		
15	MOBILIZATION	1	LS		
16	TREE AND ROOT BALL REMOVAL	7	EA		
TOTAL BASE BID					

BIDDER understands that they may be asked to provide a complete and detailed breakdown of bid item prices following opening of the bids but prior to award of contract. BIDDER also hereby certifies that the bid prices for each component of the project will be substantiated by submittal of a detailed cost breakdown of all components of the PROJECT to the ENGINEER prior to release of any payments to the BIDDER for work performed.

BIDDER understands and acknowledges that the bid items shown in this proposal represent a summary of major components of construction required. The bid price for each item shall include the cost of all adjacent or related items that are shown on the plans, are called for in the specifications, or are otherwise necessary to provide completely the improvements.

BIDDER agrees that this bid shall be good and may not be withdrawn for a period of ninety (90) consecutive calendar days after the scheduled closing time for receiving bids.

BIDDER understands that the City has the right to waive any informalities and maintains the right to reject any or all bids.

The undersigned agrees to enter into a contract within seven (7) days from notice of award should this proposal be accepted, and enter into bonds with good and sufficient securities, to complete the work on or before a date to be specified in the Notice to Proceed, and to fully complete the project within 30 consecutive calendar days thereafter. A penalty of $1000.00 per calendar day thereafter shall be instituted, the amount to be deducted from the contract price. In order to pay all labor employed and material used in connection with this work and to adjust all claims or liens that may arise in consequence of said work, to the satisfaction of the Director of Public Works, above said bonds shall also indemnify and save harmless the said City from all damages or injuries to any person or persons, either in the employ of the contractor, his agents, servants or employees. In the event of the failure of the undersigned to enter into such contract within seven (7) days of the award, then the deposit or certified check of five percent (5%) of the total bid amount as surety is therefore forfeited to the City of Joplin.

All applicable laws, ordinances, and the rules and regulations of all authorities having jurisdiction over construction of the PROJECT shall apply to the Contract throughout.

Each BIDDER is responsible for inspecting the site and for reading and being thoroughly familiar with the CONTRACT DOCUMENTS. The failure or omission of any BIDDER to do any of the foregoing shall in no way relieve any BIDDER from the any obligation in respect to his BID.

The low BIDDER shall supply the names and addresses of the major material SUPPLIERS AND SUBCONTRACTORS when requested to do so by the OWNER.

Dated_____day of_____, 2023.

Company _____

Address _____

Signature _____

(Print Name) _____

CITY OF JOPLIN

JUSTICE CENTER SIDEWALKS 2025

Addendum No. 1

Questions and Answers Received by 6/27/2025

The Following clarifications shall be utilized for preparing bids.

1. Is the sidewalk part of the mechanical room roof?
    a. No, City personnel confirmed that the roof is separate from the sidewalk above.
2. Is there a specification on slip resistance?
    a. Yes, please refer to PROWAG 302.7 Surfaces.
3. Is the City interested in adding an item for root protection?
    a. While no other changes are being made, we are expanding the tree removal scope of work. The contract now includes the removal of seven Bradford Pear trees located on the west side of the building. This addition also impacts the required black dirt, seed, and mulch, all of which are indicated in red within the proposal above.

This addendum forms a part of the contract described above. The original Contract Documents and any prior addenda remain in full force and effect as modified by the following that shall take precedence over any contrary provisions in the prior documents.

Dan Johnson, PE
Director of Public Works

6-27-25
Date

Each bidder shall acknowledge receipt of this addendum by affixing his signature below by noting this addendum on his bid form, and by attaching this addendum to his bid.

ACKNOWLEDGEMENT
The undersigned acknowledges receipt of this addendum and the Bid submitted in accordance with information, instructions and stipulations set forth herein.

Bidder: _____

Signed By: _____

Date: _____

EXIST. ISLAND AND (1) TREE TO BE REMOVED AND PUT BACK AS 8" FIBER REINFORCED CONC. PAVEMENT APPROXIMATELY 48 SQ. YDS AND INSTALL 43 L.F. OF CURB AND GUTTER CURB IS TO BE PAINTED TRAFFIC YELLOW 43 L.F.

2.00

10.00

REMOVE MARKINGS AT LAST 3 PARKING STALLS AND CREATE 3 NEW STALLS AS SHOWN MATCH EXISTING STALL DEPTH

S. VIRGINIA AVE.

PAINT CURB ONLY "TRAFFIC RED" BEGINNING NORTH SIDE OF ADA LANDING TO BUILDING 107 L.F.

TYPE "B" ADA RAMP SEE C.O.J. STANDARD DETAILS APPROXIMATELY 39 SQ. YDS AND 39 LF OF CURB AND GUTTER

PAINT CURB ONLY "TRAFFIC YELLOW" BEGINNING SOUTH SIDE OF ADA LANDING TO ADA LANDING SOUTH 134 L.F.

1 REMOVE THESE (7) BRADFORD PEAR TREES

STOP REMOVAL AND REPLACEMENT OF EXISTING SIDEWALK AT NEWER JOINT AS SHOWN

CONTRACTOR IS TO INSTALL EXPANSION JOINT AT THE BUILDING IN THESE 3 LOCATIONS THIS SHOULD BE INCLUDED IN THE PRICE OF THE 6" SIDEWALK

3 FLAG POLE BASES AND (1) DRAIN THIS LOCATION (FIELD VERIFY)

SIDEWALK IN THIS LOCATION IS LOCATED OVER A MECHANICAL ROOM (FIELD VERIFY)

TYPE "D" ADA RAMP SEE C.O.J. STANDARD DETAILS APPROXIMATELY 35 SQ. YDS AND 46 L.F. OF CURB AND GUTTER

PAINT CURB ONLY "TRAFFIC YELLOW" BEGINNING EAST SIDE OF ADA LANDING TO EAST SIDE OF SIDEWALK AT THE EMPLOYEE ENTRANCE 170 L.F.

RETAINING WALL DRAINAGE CONTRACTOR TO INSTALL ¼" DIAMOND STEEL PLATE AT 2' IN WIDTH FLUSH WITH NEW SIDEWALK. CONTRACTOR IS TO ENSURE DRAINAGE TO ROAD BENEATH STEEL PLATE SEE DETAIL 1S2 (FIELD VERIFY)

CONTRACTOR IS TO POUR AROUND EXISTING STRUCTURE AND IS TO PROVIDE CONTROL JOINTS AT RE-ENTRANT CORNERS TO PREVENT SLAB FROM CRACKING (EVALUATE EXIST. SLAB CRACKING)

CONTRACTOR IS TO LEAVE EXISTING ADA RAMP IN PLACE

NOTE:
CONTRACTOR IS TO FIELD VERIFY THAT THE SIDEWALK IS 10'-0" WIDE PRIOR TO ORDERING MATERIAL AT THIS LOCATION.

2'-0" x 10'-0" x ¼" DIAMOND STEEL PLATE REQD. FOR COVER ABOVE TRENCH DRAIN

2'-0 ¼" OPNG.

(2) 3 x 3 x ⅜" STEEL ANGLES 10'-0" IN LENGTH EA. SIDE W/ 1/2" HEADED STUDS 2" MIN. SPACED EVENLY AT 1'-6" o/c BEGINNING IN THE CENTER

6" FIBER REINFORCED CONC. SIDEWALK SEE COJ STANDARD DETAILS

DETAIL 1S2
¾" = 1'-0"

CONTRACTOR IS TO MOVE NO PARKING SIGN SOUTH TO GREEN SPACE THIS LOCATION

CONTRACTOR IS TO REMOVE CONNECTING SLAB

START AT NEWER SIDEWALK AND GO EAST APPROXIMATELY 201 L.F. AS SHOWN

E. 3RD ST.

S. PENNSYLVANIA AVE.

GRAPHIC SCALE
0 10 20 40
(IN FEET)
1 INCH = 20 FEET

GENERAL NOTES:
1. CONTRACTOR SHALL, AT HIS EXPENSE, SET & MAINTAIN ALL LINE & GRADE STAKES.
2. CONTRACTOR SHALL GRADE ALL EXISTING STREETS, ALLEYS, & DRIVES TO MEET NEW CONST.
3. CONTRACTOR SHALL FIELD VERIFY ALL UTILITY LOCATIONS BEFORE BEGINNING NEW CONST.
4. ALL WORK SHALL CONFORM TO THE CITY OF JOPLIN STD SPECS UNLESS OTHERWISE NOTED.
5. ALL WORK SHALL BE IN ACCORDANCE WITH THE WORK ZONE SAFETY GUIDELINES OF PART VI OF THE MUTCD & WITH THE BARRICADING SECTION OF THE CITY OF JOPLIN SAFETY MANUAL.
6. ALL PEDESTRIAN FACILITIES SHALL CONFORM TO THE APPLICABLE REQUIREMENTS OF THE ADA.
7. CONTRACTOR SHALL, AT HIS EXPENSE, PROVIDE ACCESS TO PRIVATE PROPERTY AT ALL TIMES.
8. CONTRACTOR SHALL, AT HIS EXPENSE, RETAIN THE SERVICES OF A PLS LICENSED IN MISSOURI, WHO SHALL BE RESPONSIBLE FOR RESTORING ANY INCIDENTALLY DAMAGED SURVEY MONUMENTS NOT SCHEDULED FOR REMOVAL AS PART OF CONST PROJECT. CONTRACTOR SHALL NOTIFY THE CITY OF JOPLIN OF ANY MONUMENTS DAMAGED BY ANY OUTSIDE PARTY.

MISSOURI ONE CALL SYSTEM, INC. 1-800-344-7483 STOP - CALL BEFORE YOU DIG

Justice Center Sidewalk Improvements.dwg

JOPLIN MISSOURI

CITY OF JOPLIN, MISSOURI
PUBLIC WORKS DEPARTMENT
DIVISION OF ENGINEERING

ADDRESS: 602 S MAIN ST 64801
PH NO: 417-624-0820 EXT 1530
FAX NO: 417-625-4738
E-MAIL: DJOHNSO1@JOPLINMO.ORG

REV DATE:	REVISION:
06/27/2025	PROJECT CHECK

SVYD BY: N/A
PNT FILE: N/A.TXT
SVY DATE: N/A
ENGINEER: JOHNSON

ACAD DWG FILE & PATH NAME: STREET\JUSTICE CENTER
SCALES: HORZ: 1" = 20' VERT: N/A

DWN BY: CPRINGLE
CKD BY: JOHNSON
APD BY: JOHNSON
DATE: 06/2025

PROJECT
NEW SIDEWALK IMPROVEMENTS FOR CITY OF JOPLIN JUSTICE CENTER

PLAN NO: 8548
SHEET 2 of 2