CITY OF JOPLIN
ADDENDUM NUMBER 1

Issued to all Bid Document Holders of Record.

Date: 2/18/2025

Project Name: Joplin Streets Mill and Overlay 2025

This addendum forms a part of the contract described above. The original Contract Documents and any prior addenda remain in full force and effect as modified by the following that shall take precedence over any contrary provisions in the prior documents.

1) **The following are questions from the pre-bid or emailed in and their answers:**

   Q. Will night work be allowed?
   A. Night work will not be allowed.

   Q. What coordination will be required with the Railroad?
   A. The City will handle the coordination with MNA RR for working near the crossings.

   Q. Will the pull off area be paved next to Jefferson Elementary School on McKinley Ave?
   A. Yes.

   Q. Is Forest Park Cemetery 2" thickness even though it is directly on base rock?
   A. Yes.

   Q. Will Trackless Tack be accepted in place of SS-1?
   A. As long as it is MoDOT approved, we will allow it.

   Q. Will anti-strip be required in the BP mix?
   A. Yes, we want the additive in the mix.

   Q. How will the bid be awarded?
   A. Bid will be awarded based on either base bid or any combination of Base and Alternates at the City's choosing.

2) **The Proposal is updated to add the following items (make sure to use the updated proposal when turning in bids):**
   a. **An item is added to the base bid for W 33rd Street. It is currently just base rock.**
   b. **The milling on the Alternates is changed to reflect the 1.5" that we are calling for on paving.**
   c. **An item has been added to base bid for yellow striping on Perkins.**
   d. **An item has been added for milling on the tennis courts. It may not be needed, but is added in case it is needed to allow proper drainage.**

Daniel Johnson, PE
Director of Public Works

2-18-25
Date

Each bidder shall acknowledge receipt of this addendum by affixing his signature below by noting this addendum on his bid form, and by attaching this addendum to his bid.

ACKNOWLEDGEMENT
The undersigned acknowledges receipt of this addendum and the Bid submitted in accordance with information, instructions and stipulations set forth herein.

Bidder: _____

Signed By: _____

Date: _____

PROPOSAL

THE UNDERSIGNED hereby proposes to furnish the labor and material for:

JOPLIN STREETS MILL AND OVERLAY 2025

In the City of Joplin, Missouri, according to the general specifications for such work on file in the office of the City Engineer and Director of Public Works, together with the terms and conditions to be stipulated in the general contract forms, now adopted by the City of Joplin, as advertised to be let on 20th day of February 2025 at 10:00 a.m. at the following prices to-wit:

	Item	***Unit***	***Quantity***	***Unit Price***	***TOTAL***
1	Asphaltic concrete 1.5” and 2" avg thickness MoDOT BP-1/ BP-2 Mix	Tons	38,522		
2	Cold Planing, 1"-2" Average (Edge Mill)	Sq Yd	164,280		
3	Cold Planing, 2" (Full Width)	Sq Yd	7,000		
4	Mobilization	LS	1		
5	Additional mobilizations	Each	2		
6	Forest Park Cemetery (2” avg thickness)	Tons	800		
7	Safety Training Center Pad (2” avg thickness)	Tons	650		
8	Public Works Center Parking Lot Expansion (3” avg thickness)	Tons	235		
9	Tennis Courts (2” thickness)	Tons	440		
10	White Thermoplastic 6’x2’ Bars (for School Crosswalks)	EA	55		
11	W. 33rd Street 3” Avg. BP-1/BP-2 Mix	Tons	75		
12	4” White Pavement Marking (Thermoplastic)	LF	1,250		
13	Tennis Courts Cold Planing, 2" (Full Width)	SY	4,000		
		TOTAL			

ALTERNATE 1 – Connecticut Avenue – 32nd Street to Campbell Pkwy

	Item	***Unit***	***Quantity***	***Unit Price***	***TOTAL***
A1	Asphaltic concrete 1.5” avg thickness MoDOT BP-1/ BP-2 Mix	Tons	4,345		
A2	Cold Planing, 1.5" (Full Width)	Sq Yd	52,667		

A3	Mobilization	LS	1		
A4	Traffic Control	LS	1		
A5	4” White Pavement Marking (Thermoplastic)	LF	17,050		
A6	4” Yellow Pavement Marking (Thermoplastic)	LF	17,540		
A7	6” White Pavement Marking (Thermoplastic)	LF	970		
A8	24” White Pavement Marking (Thermoplastic)	LF	312		
A9	White Thermoplastic 6’x2’ Bars (for School Crosswalks)	EA	13		
A10	Left Arrow (Preformed Thermoplastic)	EA	40		
A11	Bike Symbol (Preformed Thermoplastic)	EA	22		
A12	Bike Lane Arrow (Preformed Thermoplastic)	EA	22		
		TOTAL			

ALTERNATE 2 – Shifferdecker Avenue – 32nd Street to 7th Street

	Item	***Unit***	***Quantity***	***Unit Price***	***TOTAL***
B1	Asphaltic concrete 1.5” avg thickness MoDOT BP-1/ BP-2 Mix	Tons	5,760		
B2	Cold Planing, 1.5" (Full Width)	Sq Yd	69,800		
B3	Mobilization	LS	1		
B4	Traffic Control	LS	1		
B5	4” White Pavement Marking (Thermoplastic)	LF	17,060		
B6	4” Yellow Pavement Marking (Thermoplastic)	LF	24,270		
B7	6” White Pavement Marking (Thermoplastic)	LF	5,000		
B8	24” White Pavement Marking (Thermoplastic)	LF	432		
B9	24” Yellow Pavement Marking (Thermoplastic)	LF	105		
B10	Left Arrow (Preformed Thermoplastic)	EA	63		
B11	Bike Symbol (Preformed Thermoplastic)	EA	16		
B12	Bike Lane Arrow (Preformed Thermoplastic)	EA	16		
B13	Railroad Symbol (Preformed Thermoplastic)	EA	4		
		TOTAL			

Note: City reserves the right to add or delete from contract. There shall be no mobilization charges for work added over 150 tons.

ACCEPTANCE FOR PROVISION FOR ASPHALT CEMENT PRICE INDEX

Bidders have the option to accept the provision for Asphalt Cement Price Index in accordance with the Job Special Provision. The bidder must mark the box below if they choose to accept the provision. No price adjustments will be made, due to asphalt changes, for bidders who do not accept this provision.

☐ Yes □ No Asphalt Cement Price Index

The undersigned agrees to enter into a contract within fifteen (15) days from notice of award should this proposal be accepted, and enter into bonds with good and sufficient securities, to be complete this work by July 31, 2025. Should the undersigned fail to complete the work within the allowed working days, a penalty of $2,500.00 per calendar day thereafter shall be instituted, the amount to be deducted from the contract price. In order to pay all labor employed and material used in connection with this work and to adjust all claims or liens that may arise in consequence of said work, to the satisfaction of the Director of Public Works, above said bonds shall also indemnify and save harmless the said City from all damages or injuries to any person or persons, either in the employ of the contractor, his agents, servants or employees.

In the event of the failure of the undersigned to enter into such contract within fifteen (15) days of the award, then the deposit or certified check of five percent (5%) of the total bid amount as surety is therefore forfeited to the City of Joplin.

The original signed proposal must be submitted to the Public Works Director, Public Works Office, 602 South Main Street, Joplin, MO 64801, 20th day of February at 10:00 a.m. The Contractor certifies that the information provided by it in its offer is accurate and complete. The execution of this proposal is certification that the undersigned Contractor has read and understands the instructions, terms, conditions and specifications of this solicitation, and agrees to fulfill the requirements of any awarded contract at the prices offered. By executing this offer, the Contractor further certifies that they are duly authorized to execute contracts on behalf of the Contractor and have obtained all necessary or applicable approvals to make this contract fully binding upon the Contractor.

Dated this _____ day of _____, 20___.

Company _____

Complete Address _____

_____

By (signature) _____