CITY OF JOPLIN

2020 EAST TOWN INFRASTRUCTURE – SANITARY SEWER
CDBG GRANT No. B-20-MC-29-0008

ADDENDUM NUMBER 1

Issued to all Bid Document Holders of Record.

Date: September 25, 2020

This addendum forms a part of the contract described above. The original Contract Documents and any prior addenda remain in full force and effect as modified by the following that shall take precedence over any contrary provisions in the prior documents.

GENERAL CLARIFICATIONS:

1. Mandatory Pre-bid Bid meeting has been rescheduled for **Sept. 29th**, 10 a.m. in the **5th Floor Study (conference room)**, Joplin City Hall.
    - Bid Opening date, time and location all remain unchanged.
2. Imbedded within this addenda is a table of information pertaining to the sewer mains scheduled to receive CIPP reconstruction. The source spreadsheet is available upon written request by emailing the City Engineer at cparker@joplinmo.org.
3. The Table of Contents incorrectly references the Missouri Annual Wage Order No. 24, when No. 27 was already made a part of the bid packet.

SCHEDULE OF CIPP LINE WORK

US MH #	DS MH #	Pipe Dia.	Length	Depth (Ft)	Material	Location	Open Cut Repair	Trenchless Repair	CIPP Length
M09-105	M09-65	8	260	4	CONC	Asphalt	No	Yes	260
N09-295	N09-290	8	227	5	VCP	Turf	Yes	Yes	0
N09-290	N09-285	8	400	5	VCP	Turf	Yes	Yes	0
M09-135	M09-140	8	150	6	CONC	Alley	Yes	Yes	150
N09-275	N09-55	8	370	6	CONC	Alley	Yes	Yes	370
N09-220	N09-325	8	135	6	CONC	Turf	Yes	No	0
M09-75	M09-80	8	290	8	CONC	Alley			0
M09-35	M09-30	8	185	6	PVC	Alley	No	No	0
M09-165	M09-160	8	300	6	VCP	Alley	Yes	Yes	0
	8" Dia., 0' - 6' DEEP		**2317**						**780**
M09-140	M09-145	8	105	7	CONC	Turf	No	Yes	105
N09-255	N09-260	8	65	7	CONC	Asphalt	Yes	Yes	65
M09-130	M09-135	8	230	8	CONC	Turf	Yes	Yes	0
M09-110	M09-80	8	74	8	CONC	Alley	No	Yes	74
M09-25	M09-20	8	235	8	PVC	Turf	No	No	0
M09-30	M09-25	8	190	8	PVC	Turf	Yes	No	0
M09-70	M09-80	8	155	8	CONC	Alley	No	No	0
M09-155	M09-95	8	300	9	PVC	Turf	Yes	Yes	300
O09-30	N09-160	8	70	9	CONC	Asphalt	Yes	No	0
M09-95	M09-50	8	300	10	PVC	Turf	Yes	Yes	300
N09-110	N09-45	8	320	10	VCP	Alley	No	Yes	0
N09-100	N09-105	8	360	10	VCP	Alley	No	Yes	0
N09-95	N09-100	8	350	10	PVC	Alley	Yes	Yes	0
N09-90	N09-95	8	240	10	PVC	Alley	Yes	Yes	0
N09-85	N09-90	8	330	10	CONC	Alley	No	Yes	0
N09-80	N09-85	8	405	10	VCP	Alley	No	Yes	0
N09-70	N09-75	8	165	10	CONC	Alley	No	Yes	0
M09-50	M09-55	8	20	10	PVC	Asphalt	Yes	No	0
N09-75	N09-80	8	350	10	VCP	Alley	Yes	Yes	350
M09-160	M09-90	8	290	11	CONC	Alley	Yes	No	0
M09-90	M09-45	8	320	11	VCP	Alley	Yes	Yes	0
N09-105	N09-40	8	340	12	VCP	Alley	Yes	Yes	340
M09-45	N09-40	8	370	12	PVC	Alley	Yes	Yes	370
M09-15	N09-40	8	188	12	PVC	Asphalt	Yes	No	0
	8" Dia., 6' - 12' DEEP		**5772**						**1904**
N09-65	N09-60	10	80	5	VCP	Asphalt	No	Yes	80
N09-60	N09-55	10	125	5	VCP	Asphalt	Yes	No	125
	10" Dia., 0' - 6' DEEP		**205**						**205**

CITY OF JOPLIN

9/25/2020

Chris Parker, PE
Civil Engineer II (Sanitary Sewers)

Date

Each bidder shall acknowledge receipt of this addendum by affixing his signature below by noting this addendum on his bid form, and by attaching this addendum to his bid.

ACKNOWLEDGEMENT

The undersigned acknowledges receipt of this addendum and the Bid submitted in accordance with information, instructions and stipulations set forth herein.

Bidder: _____

Signed By: _____

Date: _____