JOB SPECIAL PROVISION JSP-1100-01
CLEARING & TREE & BRUSH REMOVAL

1.0 SCOPE

Clearing, Grubbing, Tree Removal, and Brush Removal shall be in accordance with Section 1100 of the current approved City of Joplin, Standard Specifications, except as modified by this Job Special Provision.

2.0 CONSTRUCTION

Grubbing – Grubbing will not be conducted as part of this bid item. No removal of topsoil, stumps, roots or buried trees and brush is permitted under this contract.

Tree & Brush Removal - The contractor shall remove all existing trees and brush (excluding their stumps) within the limits of construction and which conflict with proposed construction items except those specifically noted to remain. The contractor shall not remove any materials from the project site. However the materials shall be placed onsite, outside of the proposed trail improvements shown in the plans.

3.0 MEASUREMENT

Clearing shall not be measured separately.

Grubbing shall not be measured separately.

Tree Removal shall not be measured separately but shall be considered part of the Lump Sum pay item ‘Clearing & Grubbing / Tree & Brush Removal’.

Brush Removal shall not be measured separately but shall be considered part of the Lump Sum pay item ‘Clearing & Grubbing / Tree & Brush Removal’.

4.0 PAYMENT

Payment for “Clearing & Grubbing / Tree & Brush Removal” shall be at the contract lump sum price and shall include the cost of furnishing all labor, equipment, tools, and materials, and the performance of all work necessary to complete removals.