City of Joplin
Notification to Bidders

Issued to all Bid Document Holders of Record.

Date: 8/4/2020

Project Name: Fire Station Concrete Apron Approach Project

This notification serves to clarify Sheet Number C103 which was sent as part of Addendum 1.

1. The Sheet C103 calls out expansion joints at all edges of the concrete except at curb and gutter. The edges abutting the existing asphalt are to be isolation joints, and the edges along the building/foundation should also be isolation joints as is called out in the Concrete Pavement Notes, not expansion joints.
2. All other joints, in both directions, are to be contraction joints except that expansion joints are to be installed at every 5^{th} transverse joint in each direction as called out by the note in the expansion joint standard detail.
3. There are no planned longitudinal joints; the detail is only shown in case a situation were to arise in which a longitudinal joint is needed.

Thanks,

Dakota Rusk