CITY OF JOPLIN
ADDENDUM NUMBER 1

Issued to all Bid Document Holders of Record.

Date: March 11, 2020

Project Name: Police Parking Lot Fence

This addendum forms a part of the contract described above. The original Contract Documents and any prior addenda remain in full force and effect as modified by the following that shall take precedence over any contrary provisions in the prior documents.

1) **An additional: Bid needed for replacement of the gate at the Police Parking Lot. This is because the current gate cannot be used in the opposite direction.**

2) **An additional: There will need to be a loop installed under the asphalt to allow the gate to open for vehicles leaving the parking lot and a redundancy for safety reasons so the gate will not shut while a vehicle is still in the gate line.**

3) **An additional**

David K. Hertzberg, PE
Director of Public Works

3/11/2020
Date

Each bidder shall acknowledge receipt of this addendum by affixing his signature below by noting this addendum on his bid form, and by attaching this addendum to his bid.

ACKNOWLEDGEMENT
The undersigned acknowledges receipt of this addendum and the Bid submitted in accordance with information, instructions and stipulations set forth herein.

Bidder: _____

Signed By: _____

Date: _____

PROPOSAL

THE UNDERSIGNED hereby proposes to furnish the labor and material for:

Joplin Justice Center Parking Lot Fencing

in the City of Joplin, Missouri, according to the general specifications for such work on file in the office of the Director of Public Works, together with the terms and conditions to be stipulated in the general contract forms, now adopted by the City of Joplin, as advertised to be let on the 17th of March, 2020:

	Item	Quantity	Unit	Unit Price	Ext. Price
1	Install 6 ft Chain Link Fence includes following	430 FT	LS		
2	Fabric 9 GA				
3	2 7/8 terminal posts 40 wt				
4	2 3/8 line post 20 wt				
5	1 5/8 top rail 20 wt				
6	Barb arms with barbwire				
7	Move and install 20 ft cantilever gate				
8	Move and install 6 ft walk gate				
9	Post set at 24 in with concrete				
10	Cantilever gate post at 36-48 in				
11	Remove 210 ft existing fence				
12	Cut post at ground level				
13	Final fence placement				
14	Labor				
15	Additional costs as needed				
16	Replace & Install new vehicle gate				
17	Install loop in asphalt				
	Total Fence and installation				
	Alternate Bid				
18	Repair and Replace damaged north side fence	50 FT	LS		
19	Repair and Replace damaged north side gate				
20	Labor				
21	Additional costs as needed				
				Grand Total	

The undersigned agrees to enter into a contract within fifteen (15) days from notice of award should this proposal be accepted, and enter into bonds with good and sufficient securities, to complete this work within Ninety (90) CALENDAR DAYS. Should the undersigned fail to complete the work within the allowed working days, a penalty of One HUNDRED DOLLARS ($100.00) per calendar day thereafter shall be instituted, the amount to be deducted from the contract price. In order to pay all labor employed and material used in connection with this work and to adjust all claims or liens that may arise in consequence of said work, to the satisfaction of the Director of Public Works, above said bonds shall also indemnify and save harmless the said City from all damages or injuries to any person or persons, either in the employ of the contractor, his agents, servants or employees. In the event of the failure of the undersigned to enter into such contract within ten days of the award, then the deposit or certified check of five percent (5%) of the total bid amount as surety is therefore forfeited to the City of Joplin.

Dated _____ day of _____, 20 ____.

Address _____

COMPANY_____ BY _____
Signature