CITY OF JOPLIN
ADDENDUM NUMBER 1

Issued to all Bid Document Holders of Record.

Date: 2/1/2021

Project Name: On call Fence Repair and Installation

This addendum forms a part of the contract described above. The original Contract Documents and any prior addenda remain in full force and effect as modified by the following that shall take precedence over any contrary provisions in the prior documents.

1) Attachment titled, "Fence for Storage Building". This will be used at part of the scoring to establish the winning bidder.
2) Date change for Bid Opening: 10:00 a.m. February 5, 2021

David K. Hertzberg, PE
Director of Public Works

2/1/2021
Date

Each bidder shall acknowledge receipt of this addendum by affixing his signature below by noting this addendum on his bid form, and by attaching this addendum to his bid.

ACKNOWLEDGEMENT
The undersigned acknowledges receipt of this addendum and the Bid submitted in accordance with information, instructions and stipulations set forth herein.

Bidder: _____

Signed By: _____

Date: _____

CITY OF JOPLIN

Storage Building Fence

Total length of fence is 508 feet, 6 feet in height with 3 strand of barb wire at top

Vehicle Fence and a pedestrian Fence; 1 – 16 foot swing drive gate. 2- 4-foot pedestrian gates

QTY	Description	Unit Price	Line Total
	9 gauge fabric		
	40 wt 1 7/8 terminal post		
	20 wt 2 3/8 line post		
	Barb Arms and Barb Wire		
	1-16 ft double swing drive gate		
	2-4 ft walk gates		
	Gates 1 5/8 20 wt frame		
	Drive Gate 4 in 40 wt posts		
	Gates Commercial hinges		
	Gates Lockable (Padlock)		
	Post set in Concrete		
508 Ft	Total install all labor and material included		